ROYALTY CALCULATION

Name of Work : Improvements of roads & drains at Ravindra nagara and other surrounding area in Ward No 13 Mallasandra, Shettyhalli sub Division

Plain Cement Concrete 1:3:6			
Description	Qty in Cum	Constant	Total Qty
Sand	103.07	0.465	47.93
Jelly	103.07	0.892	91.94
Cement Concrete Pavement			
Sand	235.29	0.43	101.17
Jelly	235.29	0.69	162.35

Sl	Items	Qty	Rate	Amount
1	Sand	149.10	138.00	20576.00
2	Jelly	254.29	126.00	32040.00
			Total	52616.00

Asst.Engineer
Ward No 13

Asst.Executive Engineer
Shettyhalli Sub Division

Scanned By Scanner Go